



City of Jacinto City Asphalt Overlay Project 2026

The City of Jacinto City is accepting bids for Type D 2" Asphalt to overlay existing residential streets within the city limits. Contractors will be responsible for all labor cost, material, traffic setup (lane closure signage) and notification to residents. The contractor is to ensure grading of asphalt meets Harris County specifications for proper drainage and installation. Bids must be submitted at City Hall, 1301 Mercury Drive by 5:00 p.m. on September 10, 2026 and will be opened at the regularly scheduled Council Meeting on said date at 10301 Market Street at 6:00 p.m. All bids submitted to the City of Jacinto City must be accompanied by a bid bond in the amount of 5% of total bid. A copy of the RFP can be requested by e-mail christal.rodriguez@jacintocity-tx.gov or picked up at City Hall, 1301 Mercury Drive, Jacinto City, TX 77029.

Scope of work: The restoration of several sections of residential streets in the city. Point repairs of existing base material must be standard black base material, bringing all manhole rings and water value boxes up to grade and 2" asphalt overlay with type D rated asphalt.

The City reserves the right to reject any/or all bids, to waive any/or all technicalities and to accept any bid or part thereof which in the opinion of the City Council is most advantageous to the city.



City of Jacinto City Asphalt Overlay Project 2026 Bid Form Sheet

Description of each project area:

1. **Kerbey:** starting at Palestine headed South to Burman: Price is to include materials type D 2" asphalt overlay, tack oil, base material level up, base material for any repairs, proper intersection cross overs / tie in.

Estimated 955 Linear Feet

Total amount Kerbey # 1 _____

2. **Palestine:** starting at Kerbey headed East to Holland: Price is to include materials type D 2" asphalt overlay, tack oil, base material level up, base material for any repairs, proper intersection cross overs / tie in.

Estimated 1,565 Linear Feet

Total amount Palestine # 2 _____

3. **Chadwick:** Starting at Kilroy going East to Flint. Price is to include materials type D 2" asphalt overlay, tack oil, base material level up, base material for any repairs, proper intersection cross overs / tie in.

Estimated 480 Linear Feet

Total amount Serpentine # 3 _____



**City of Jacinto City
Asphalt Overlay Project 2026
Bid Form Sheet**

Description of each project area:

4. **Serpentine:** starting at Rail Road headed South 150 linear feet: Price is to include materials type D 2" asphalt overlay, tack oil, base material level up, base material for any repairs, proper intersection cross overs / tie in.

Estimated 150 Linear Feet

Total amount Serpentine # 4 _____

5. The contractor provides pricing by square footage for various pothole repairs throughout city limits. Price includes materials type D 2" asphalt overlay, tack oil, base material for any repairs and squaring up patch.

Total amount per square foot pothole repair # 5 _____

Grand total amount for all sections _____

Please write out total bid amount: _____

